BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of work: Estimate for Improvements Road, Drain Removing resetting and covering slab in Ward No. 05

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	947.47	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	96.48	Rupees Ninety Six and Forty Eight Paise Only
2	990.00	Removing B.S Slab of Drain and stacking	Sqm	72.95	Rupees Seventy Two and Ninety Five Paise Only
3	990.00	Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	89.42	Rupees Eighty Nine and Forty Two Paise Only
4	1508.10	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick	Sqm	738.90	Rupees Seven Hundred Thirty Eight and Ninety Paise Only
5	133.85	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5726.51	Rupees Five Thousand Seven Hundred Twenty Six and Fifty One Paise Only
6	22.32	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per	cum	4926.42	Rupees Four Thousand Nine Hundred Twenty Six and Forty Two Paise Only
7	16.74	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Sqm	5888.88	Rupees Five Thousand Eight Hundred Eighty Eight and Eighty Eight Paise Only
8	43.99	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications.	Sqm	301.21	Rupees Three Hundred One and Twenty One Paise Only
9	73.89	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	6214.80	Rupees Six Thousand Two Hundred Fourteen and Eighty Paise Only
10	37.20	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	114.13	Rupees One Hundred Fourteen and Thirteen Paise Only

ಕ.ಅ.(ಬ್ಯಾ.ವ)

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
11	15.40	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M25 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications.	Cum	7072.54	Rupees Seven Thousand Seventy Two and Fifty Four Paise Only
12	1.39	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.	Qtl	71310.20	Rupees Seventy One Thousand Three Hundred Ten and Twenty Paise Only
13	1299.20	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	1102.47	Rupees One Thousand One Hundred Two and Forty Seven Paise Only
14	1461.60	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shutterng machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1856.67	Rupees One Thousand Eight Hundred Fifty Six and Sixty Seven Paise Only
15	268.60	KSRRB M800-20: Tubular steel railing of medium weight steel channel (ISMC series) 100 mm x 50 mm :- providing, fixing and erecting 50 mm dia steel pipe railing in 3 rows duly painted on medium weight steel channels (ISMC series) 100 mm x 50 mm, 1.2 meter high above ground, 2m center to center, complete as per approved drawings as per specifications,	Rmtr	1520.04	Rupees One Thousand Five Hundred Twenty and Four Paise Only
16	947.47	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	Cum	81.16	Rupees Eighty One and Sixteen Paise Only

5/03

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

5/03

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Chief Engineer
Yelahanka Zone
Jnath Bangalore Mahanagara
Rangalore 92